SUPPORT

(Society for upliftment of People with People's organisation and Rural Technology)

Ref. No. 8677-A/Oct/2026

Date : 10/10/202

To
All Vendors
India

Dear All
Sub - Quotation Required for Jal Minar in Bandarchuan village of Pathalgadda block of Chatra district, Jharkhand

Proposed Estimate for Concrete based 5000 litre capacity Jalminar

Sl no	SOR item no	Particular	unit	No	length in ft	Width in ft	height/Depth in ft	Quantity	Quantity in Cum	Rate	Amount Rs
1	5.1.1	Earth Cutting work for foundation with hard soil by hydraulic machine									
		For RCC Piller	Cum	4	4.00	4.00	5.00	320.00	9.07		
		For soak pit	Cum	1	5.00	5.00	4.00	100.00	2.83		
	5.1.10	Sand filling work	Cum	4	4	4	0.16	10.24	0.29		
	5.3.1.1	PCC work	Sq M	4	4	4	0.33	21.12	1.96		
2	5.3.13	R.C.C Column foundation and superstructure									
		RCC Column for Foundation	Cum	4	1.67	1.67	4.5	50.20	1.42		
		For RCC Column For Superstructure	Cum	4	1.250	1.250	10.00	62.50	1.77		
		RCC Grade beam (long Wall)	Cum	8	7.50	1.25	0.50	37.50	1.06		
		Total							4.25		
3	5.3.11	RCC Roof work									
		Ground floor roof(1:1.5:3)	Cum	1	10	10	0.41	41.00	1.16		
		For Sock pit	Cum	1	5	5	0.41	10.25	0.29		
4	5.5.5.a	MS tor required for RCC work 100Kg/cum	Kg						570.68		
5	5.2.25	Providing 125mm thick brick jali in cement mortar(1:6) in foundation for sock pit	Cum	4	4.83	0.83	4	64.14	1.82		
6	5.2.10	Brick Masonary work on super structure structure (Parapet work) Long wall	Cum	2	10	0.83	4	66.40	1.88		
		Short Wall	Cum	2	8.34	0.83	4	55.38	1.57		
7	5.7.2	Plaster work 12mm thick cement Plaster (1;4)									
		Column	sqm	4	10.00	6.00		240.00			
		Roof	sqm	1	10.00	10.00		100.00			
		Parapet wall outer area	sqm	4	10.00	4.00		160.00			
		Parapet wall Inner area and top	sqm	4	8.33	4.42		147.27			
		Total						647.27	60.21		
8	5.8.2	White washing tree coat over new surface do-do(as per Plaster surface)	sqm						60.21		
										Total Rs	
9		GST 18%									
10		Transportation of materials For structure	LS								
11		Sign board	Rs								
										SubTotal Rs	

Registered Office : At & P.O. - Mandu, Dist. : Ramgarh, Pin 825316 (Jharkhand). Mob. : 09431185632/09934509376

Administrative Office : DVC Colony, Behind Hanuman Mandir, Hazaribag - 825301(Jharkhand). Phone : 06546-266742, Mob. 9431185632
Email : bsguptahzb@rediffmail.com / supporthzb@gmail.com

Branch Offices :
BOKARO 216, Co- Operative Colony, B.S. City, Bokaro, Pin - 827001, Mob.: 7004325481
DUMKA At: Masalia, Old PHC Road, PO Ranga Masalia, Dist. Dumka, Mobile-7061153221
KODERMA H/o Amarchand Yadav, Near Middle School, Mahugai, At&PO-Chandwara, Dist. Koderma-825409
WEST SINGHBHUM 2nd Floor, Sanjivani Hospital Complex, Jagannathpur Block, West Singhbhum-833203 Mb.: 7992361799
GIRIDIH Behind Statistical Office, Near Jhanda Chowk, Giridih

Website : www.supportjharkhand.org

Secretary
SUPPO